

DATUM IN THE NEWS

NEWSPRINTERS POST PRESS HALL RESIN FLOORING INSTALLATION

The Post Press Hall works seven days a week and the only available time for any flooring installation is between 4.00am and 8.00pm



Within this window of opportunity 16 hours daily the challenge was to prepare the existing concrete slabs by vacuum controlled diamond grinding to provide a good bonding surface, this operation being carried out in and around all the built in operational equipment.

To achieve this demanding programme the floor finish had to be installed and fully cured for 100% production by 8.00am daily.

To deliver the programme Datum Industrial Flooring Limited had two teams on site the first one carrying out the diamond grinding preparation and the other priming and installing the new floor finishes.

The approximate 3,000m² area was divided into sections according to the particular press operations and which day of the week it was.

To ensure this extremely demanding programme was achieved Datum Industrial Flooring Limited partnered with Resin Surfaces Limited who supplied all the rapid cure no odor resin materials which made this demanding project achievable, the products used were Resuprime FH and Resufloor FH in colour flint.

This contract was another example of the Datum partnering philosophy at work, and was made possible by the detailed planning and flexible working arrangements agreed between Newsprinters management, Datum Industrial Flooring Limited project management and Resin Surfaces Limited.

For further details please contact

Datum Industrial Flooring Limited
Unit 21 Lambs Business Park
Tilburstow Hill Road
South Godstone
Surrey RH9 8LJ

T:0845 9000 342 F:01342 893 165 E:info@datum-flooring.co.uk www.datum-flooring.co.uk

www.datum-flooring.co.uk www.resinsurfaces.co.uk