

REFURBISHMENT AT NEXT ENDERBY



IRL were delighted when awarded this kitchen refurbishment project for Next at Enderby. The Main Contractor was Graham Taylor of Thurmaston in Leicester.

IRL Group went in over the Christmas period to remove all of the existing vinyl sheet flooring and adhesive. The concrete floor was then prepared using concrete planers and diamond grinders, all dust and debris was removed from the preparation in sealed containers. Altrocrete PU Polyurethane Screed was applied to all the floor areas, cove skirting was formed using Altro Render Grade Screed finished into a Stainless Steel Birds Beak Detail. An epoxy coating was then applied to the internal concrete pillars.

The works were completed within the specified timescale, Graham Taylor is thrilled with the system and with IRL's ability to operate within the requested time schedule, delivering a top quality finished product.

Jan 09

IRL Group Ltd
Loughborough / 01509 217101 / www.irlgroup.co.uk